PLANTING LEGEND - THIS SHEET

SYM.	BOTANICAL NAME	COMMON NAME	QTY.	SIZE	REMARKS
TREES -					
CD	CERCIDIUM "DESERT MUSEUM"	HYBRID PALO VERDE	2	24"B.	STANDARD
CT	CHITALPA TASH. 'PINK DAWN'	NCN	23	24"B.	STANDARD
QI	QUERCUS LEX	HOLLY OAK	9	24"B.	STANDARD
YB	YUCCA BREVIFOLIA	JOSHUA TREE	39		FROM LIST DATED 8/10/09 OF MATERIAL ON SITE
SHRUBS -					
BM	BAILEYA MULTIRADIATA	DESERT MARIGOLD	21	1G.	
BL	BERLANDIERA LYRATA	CHOCOLATE FLOWER	28	1G.	
CE	CALLIANDRA BRIOPHYLLA	FAIRY DUSTER	27	5G.	
CN	CASSIA NEMOPHILA	DESERT CASSIA	44	5G.	
CM	CHRYSACTINIA MEXICANA	DAMIANITA	24	1G.	
CL	COTONEASTER DAMMERI "LOWIFAST"	BEARBERRY COTONEASTER	32	1G.	
DA	DALEA GREGGII	TRAILING INDIGO BUSH	67	1G.	
DW	DASYLIRION WHEELERI	DESERT SPOON	16	5G.	
GL	GAURA LINDHEIMERI 'WHIRLING BUTTERFLIES'	NCN	22	1G.	
HP	HESPERALOE PARVIFLORA	RED YUCCA	35	5G.	
LT	LEUCOPHYLLUM CANDIDUM "THUNDER CLOUD"	VIOLET SILVER LEAF	30	5G.	
ML	MELAMPODIUM LEUCANTHUM	BLACKFOOT DAISY	14	1G.	
MC	MYRTUS COMMUNIS	MYRTLE	11	5G.	
OV	OPUNTIA VIOLACEA	NCN	10	15G.	
PC	PENSTEMON CENTRANTHIFOLIUS	SCARLET BUGLER	24	1G.	
PS	PENSTEMON SUPERBUS	NCN	18	1G.	
SC	SALVIA CLEVELANDII	CLEVELAND SAGE	12	5G.	
SG	SALVIA GREGGII	AUTUMN SAGE	34	5G.	
SA	SPHAERALCEA AMBIGUA	APRICOT MALLOW	28	1G.	
VINES -					
FR	FICUS REPENS	CREEPING FIG	1	5G.	TRAIN ON WALL
GS	GELSEMIUM SEMPERVIRENS	CAROLINA JESSAMINE	6	15G.	TRAIN ON TRELLIS

RIVER-ROCK GROUNDCOVER -
"DESERT BROWN COBBLE" FROM WHITEWATER ROCK & SUPPLY, (760) 325-2747, 3" TO 5" SIZE
- FOR ON-SITE INSTALLATION AND IN RIGHT OF WAY (ROW) AREA AT BACK OF SIDEWALK INSTALL OVER TYPAR OR EQUAL WEED CONTROL FABRIC SO THAT NO FABRIC IS SHOWING IN GAPS IN STONES (APPROX. 4,270 SQ. FT.). FOR INSTALLATION IN HWY. 62 MEDIAN (APPROX. 2,585 SQ. FT.) INSTALL PER CAL-TRANS "ROCK BLANKET" DETAIL & SPECIFICATIONS SHT. 5 OF 6.

DECOMPOSED GRANITE GROUNDCOVER -
ALL PLANTING AREAS THAT DO NOT RECEIVE "DESERT BROWN COBBLE" GROUNDCOVER SHALL BE MULCHED WITH 1/4"MINUS DECOMPOSED GRANITE LITE AT A MINIMUM DEPTH OF 2". CONTRACTOR SHALL COMPACT BY WATERING TWICE AFTER INSTALLATION

BOULDERS - WHITEWATER ROCK & SUPPLY (760) 325-2747, GREY RIVER-ROCK BOULDERS, SEE DETAIL

(1) MEDIUM SIZE GRANITE BOULDER (APPROXIMATELY 2'X3'X3'), (29 MED. BOULDERS)

(2) LARGE SIZE GRANITE BOULDER (APPROXIMATELY 3'X3'X4'), (46 LARGE BOULDERS)

PLANTING NOTES -

1. CONTRACTOR SHALL EXERCISE CARE IN LOCATING UNDERGROUND UTILITIES PRIOR TO DIGGING, RESOLVING ALL CONFLICTS IN FIELD.
2. CONTRACTOR SHALL INSTALL DEEP ROOT UB-24 OR APPROVED EQUAL ROOT CONTROL PRODUCT W/ TREES PLANTED WITHIN 7' OF PAVING OR CURBS, PER MANUFACTURERS SPECIFICATIONS. THIS SHALL INCLUDE THE USE OF 3/4" CRUSHED AGGREGATE AROUND THE OUTSIDE OF THE BARRIER AT EACH TREE PER THE DETAIL.
3. CONTRACTOR SHALL INSTALL PLANTING AS PER THESE PLANS, AND SPECIFICATIONS.

CAL-TRANS NOTE:

ALL WORK PERFORMED IN CONNECTION WITH HIGHWAY PLANTING WITHIN THE STATE RIGHT OF WAY SHALL CONFORM TO THE PROVISIONS IN SECTION 20-4 OF CALTRANS 2006 STANDARD SPECIFICATIONS.

CAL-TRANS "ROCK BLANKET" IN MEDIAN, SEE DETAIL 1 W/ SPEC. ON SHT. 5 OF 6

TYPICAL NEW SIGNAGE, SEE ARCH. PLANS

EXTENT OF CAL-TRANS ROW

TWENTYNINE PALMS (HWY 62)

WARREN VISTA AVE

SIDEWALK

FRESH & EASY
GROCERY/RETAIL

PAD A

RITE AID

SAN BERNARDINO FLOOD CONTROL DISTRICT

MATCHLINE SEE SHEET 5

PLANTING PLAN
SCALE: 1" = 20'

Underground Service Alert
Call: TOLL FREE
1-800
422-4133
TWO WORKING DAYS BEFORE YOU DIG

Registered Landscape Architect
Robert Mekjian
NO. 3183
EXP. 05-31-10
STATE OF CALIFORNIA
SIGNATURE & DATE

LOST WEST
A CALIFORNIA CORPORATION
LANDSCAPE ARCHITECTURE
GARDENS ◦ PARKS ◦ CITIES
PO BOX 4548 Carlsbad, CA 92018
5208 Townsend Ave. Los Angeles, CA 90041
TEL: (760) 434-5790 OR (323) 258-8214

0810 Warren Vista, Yucca Valley
PLAN DATE: 09/30/09
PLOTTING HISTORY-
09/30/09 - Version 1

MARK	REVISIONS	BY	APPR.	DATE

BENCH MARK:

DRAWN BY:
CHECKED BY:
RECOMMENDED BY:

WARREN VISTA RETAIL CENTER
HWY. 62 & Warren Vista Ave., Yucca Valley

LANDSCAPE –
PLANTING PLAN

DRAWING NO.

SHEET 4 OF 6 SHEETS