



May 5, 2023

Project No. 23143

Mr. Daniel Patneau
DRP Enterprises, LLC
PO Box 4428
Palm Springs, CA 92263

Subject: Geotechnical Investigation Report
Proposed Lomita Boutique Campground
APN 0596-271-07, Town of Yucca Valley, California
5022 Lomita Lane

Dear Mr. Patneau:

In accordance with your request and authorization, we are presenting the results of our geotechnical investigation for the proposed Lomita Boutique Campground project at APN 0596-271-07, in the Town of Yucca Valley, County of San Bernardino, California. The purpose of this investigation has been to evaluate the subsurface conditions at the site and to provide geotechnical engineering recommendations for the proposed construction.

Based on our findings, the proposed project is geotechnically feasible, provided that the recommendations in this report are incorporated into the design and are implemented during construction of the project. This report was prepared in accordance with the requirements of the 2022 California Building Code and the Town of Yucca Valley requirements.

We appreciate the opportunity to be of service on this project. Should you have any questions regarding this report or if we can be of further service, please do not hesitate to contact the undersigned at (657) 888-4608 or info@ntsgeo.com.

Respectfully submitted,
NTS GEOTECHNICAL, INC.

A handwritten signature in black ink, appearing to read "Nadim Sunna".

Nadim Sunna, M.Sc., Q.S.P., P.E., G.E. 3172
Principal Engineer



Table of Contents

INTRODUCTION.....	3
SITE AND PROJECT DESCRIPTION.....	3
SCOPE OF WORK.....	3
Background Review.....	3
Field Exploration.....	3
Geotechnical Laboratory Testing.....	4
GEOLOGIC FINDINGS.....	4
Subsurface Materials.....	4
Groundwater.....	4
GEOLOGIC HAZARDS.....	4
Faulting and Seismicity.....	4
Liquefaction and Seismic Settlement.....	5
Landslides.....	5
Flooding.....	5
Tsunami and Seiches.....	5
GEOTECHNICAL ENGINEERING FINDINGS.....	6
Expansive Soil.....	6
Hydroconsolidation.....	6
Soil Corrosion.....	6
Shrinkage.....	7
Preliminary Infiltration Testing.....	7
Excavation Characteristics.....	8
GEOTECHNICAL ENGINEERING CONCLUSIONS AND RECOMMENDATIONS.....	8
Conclusions.....	8
Site Preparation.....	8
Remedial Grading.....	9
Materials for Fill.....	11
Compacted Fill.....	11
Temporary Excavations.....	11
Building Foundation Design and Construction.....	12
Slab-On-Grade Design and Construction.....	13
Moisture Vapor Retarder.....	14
Preliminary Infiltration Design and Construction Recommendations.....	14
Asphalt Concrete Pavement Design.....	15
Exterior Flatwork/Hardscape Design Considerations.....	16
Planters and Trees.....	16
Drainage Control.....	17
Plans and Specifications Review.....	18
Construction Observation and Testing.....	18
LIMITATIONS.....	18
REFERENCES.....	20

Attachment(s): Plate 1 – Location Map
 Plate 2 – Geotechnical Map

 Appendix A – Field Exploration
 Appendix B – Geotechnical Laboratory Test Result
 Appendix C – Infiltration Test Results

INTRODUCTION

This report presents the results of our geotechnical engineering evaluation performed for the proposed Lomita Boutique Campground to be located at APN 0596-271-07, in the Town of Yucca Valley, County of San Bernardino, California. See (Plate 1, Location Map). The purpose of this study has been to evaluate the subsurface conditions at the site and to provide geotechnical recommendations related to the design and construction of the proposed structures.

SITE AND PROJECT DESCRIPTION

The project site is located at APN 0596-271-07, in the Town of Yucca Valley, California, and it is bound by existing single-family residence located at 4954 Lomita Ln on the north, Rowell Rd on the west, Lomita Lane on the east, and existing residence on the south. The nearly rectangular lot is currently vacant and occupied by native plants, brushes and trees.

It is our understanding that the proposed project consists of construction of a campground that is made up of about 20 camping structures, a club house, parking lot and roadways leading to the campground structures. Additionally, the site will be serviced by a septic system.

Detailed plans were not available during the preparation of this report, and thus this report is subject to change based on final plans.

SCOPE OF WORK

As part of the preparation of this report, we have performed the following tasks:

Background Review

We reviewed readily available background data including geologic maps, topographic maps, and aerial photographs relevant to the subject site in preparation of this report.

Field Exploration

The subsurface conditions were evaluated on April 6, 2023 by advancing five (5) hollow-stem-auger borings to maximum depth of 15 feet below the existing grade. The approximate location of the borings are shown on Plate 2 – Geotechnical Map. Detailed exploration information of soils borings are presented in Appendix A, Field Exploration.

Geotechnical Laboratory Testing

Laboratory tests were performed on selected samples obtained from the boring in order to aid in the soil classification and to evaluate the engineering properties of the foundation soils. The following tests were performed in general accordance with ASTM standards:

- In-situ moisture and density;
- #200 sieve wash;
- Consolidation;
- Direct shear; and
- Corrosion suite.

Laboratory results are presented in Appendix B of this report.

GEOLOGIC FINDINGS

Subsurface Materials

Earth materials encountered during our subsurface investigation consist of older alluvium (Qal) to the total depth of the exploration. The alluvium consists of brown, brown, dry, medium dense to dense, silty sands. The upper 3 feet of the site soils are considered loose and compressible and will require remedial grading.

Groundwater

Groundwater was not observed during our exploration to a maximum depth of 15 feet below the existing grade. Review of nearby well data (Well No. 341625N1164122W001) reveal that the highest groundwater reading is about elevation 3516 MSL, which places the groundwater at a depth of approximately 190 feet below existing grade. Groundwater conditions may vary across the site due to stratigraphic and hydrologic conditions, and may change over time as a consequence of seasonal and meteorological fluctuations, or activities by humans at this site and nearby sites. However, based on the above findings, groundwater is unlikely to impact the proposed development.

GEOLOGIC HAZARDS

Faulting and Seismicity

The site is not located within an Alquist-Priolo Earthquake Fault Zone, and based on our review of the County of San Bernardino Geologic Hazard Map, we note

that the site is also not mapped within a County designated fault zone; however, the site is located in the seismically active region of Southern California. The nearest known active fault is the Landers fault system, which is located approximately 0.3 miles from the subject site.

Liquefaction and Seismic Settlement

Liquefaction occurs when the pore pressures generated within a soil mass approach the effective overburden pressure. Liquefaction of soils may be caused by cyclic loading such as that imposed by ground shaking during earthquakes. The increase in pore pressure results in a loss of strength, and the soil then can undergo both horizontal and vertical movements, depending on the site conditions. Other phenomena associated with soil liquefaction include sand boils, ground oscillation, and loss of foundation bearing capacity. Liquefaction is generally known to occur in loose, saturated, relatively clean, fine-grained cohesionless soils at depths shallower than approximately 50 feet. Factors to consider in the evaluation of soil liquefaction potential include groundwater conditions, soil type, grain size distribution, relative density, degree of saturation, and both the intensity and duration of ground motion.

Based on our review of the County of San Bernardino County Land Use plan, Geologic Hazard Overlays, the site is not situated within an area identified to having susceptibility to liquefaction. Additionally, based on the lack of shallow groundwater, and uniform soil stratum, it is our professional opinion that potential for liquefaction and associated seismic settlement to impact the proposed improvement is considered low.

Landslides

Based on our review of the referenced geologic maps, literature, topographic maps, aerial photographs, and our subsurface evaluation, no landslides or related features underlie or are adjacent to the subject site. Due to the relatively level nature of the site and surrounding areas, the potential for landslides at the project site is considered low.

Flooding

The Federal Emergency Management Agency (FEMA) has prepared flood insurance rate maps (FIRMs) for use in administering the National Flood Insurance Program. Based on our review of the FEMA flood map, the site is located in an Area of Minimal Flood Hazard (Zone X).

Tsunami and Seiches

Tsunamis are waves generated by massive landslides near or under sea water. The site is not located on any State of California Tsunami Inundation Map for

Emergency Planning. The potential for the site to be adversely impacted by earthquake-induced tsunamis is considered to be negligible because the site is located several miles inland from the Pacific Ocean shore, at an elevation exceeding the maximum height of potential tsunami inundation.

Seiches are standing wave oscillations of an enclosed water body after the original driving force has dissipated. The potential for the site to be adversely impacted by earthquake-induced seiches is considered to be negligible due to the lack of any significant enclosed bodies of water located in the vicinity of the site.

GEOTECHNICAL ENGINEERING FINDINGS

Expansive Soil

Based on our evaluation, laboratory testing and experience with similar material types, the soils encountered near the ground surface at the site exhibit a very low expansion potential.

Hydroconsolidation

Based on our laboratory test results, and the loose nature of the upper approximately 3 feet of the site soils, the potential for hydrocollapse settlement to affect the proposed structures should be considered low to moderate. Grading recommendations to minimize hydroconsolidation are provided in this report.

Soil Corrosion

The potential for the on-site materials to corrode buried steel and concrete improvements was evaluated. Laboratory testing was performed on representative soil samples to evaluate pH, minimum resistivity, and soluble chloride and sulfate contents. The results of our corrosivity testing is presented within Appendix B of this report. General recommendations to address the corrosion potential of the on-site soils are provided below. Imported fill materials, if used, should be tested to evaluate whether their corrosion potential is more severe than those assumed.

Structural Concrete

Laboratory tests indicate that the potential of sulfate attack on concrete in contact with the on-site soils is “negligible” or “S0” exposure in accordance with ACI 318, Table 19.3.1.1. Therefore, restriction on the type of cement, water to cement ratio, and compressive strength is not required.

The aforementioned recommendations in regards to concrete are made from a soils perspective only. Final concrete mix design is beyond our purview. All applicable codes, ordinances, regulations, and guidelines should be followed in regard to the designing a durable concrete with respect to the potential for sulfate exposure from the on-site soils and/or changes in the environment.

Ferrous Metal

The results of the laboratory chemical tests performed on a sample of soil collected within the site indicate that the on-site soils are mildly corrosive to ferrous metals. Consequently, metal structures which will be in direct contact with the soil (i.e., underground metal conduits, pipelines, metal sign posts, etc.) and/or in close proximity to the soil (wrought iron fencing, etc.) may be subject to corrosion. The use of special coatings or cathodic protection around buried metal structures has been shown to be beneficial in reducing corrosion potential.

The laboratory testing program performed for this project does not address the potential for corrosion to copper piping. In this regard, a corrosion engineer should be consulted to perform more detailed testing and develop appropriate mitigation measures (if necessary).

The above discussion is provided for general guidance in regards to the corrosiveness of the on-site soils to typical metal structures used for construction. Detailed corrosion testing and recommendations for protecting buried ferrous metal and/or copper elements are beyond our purview. If detailed testing is required, a corrosion engineer should be consulted to perform the testing and develop appropriate mitigation measures.

Shrinkage

The shrinkage factor for earthwork is expected to range from 5 to 10 percent for the site soils. This estimate is based on a compactive effort to achieve an average relative compaction of 90 percent and may vary with contractor means and methods and actual comp active efforts. Subsidence is estimated to be approximately 0.10 feet. Losses from site clearing and removal of existing site improvements may affect earthwork quantity and should be considered.

Preliminary Infiltration Testing

One (1) preliminary infiltration test was performed in general conformance with the County of San Bernardino requirements. The boring is shown on the attached Plate 2 – Geotechnical Map, were excavated to a depth of 5 feet below the existing grade. The calculated observed infiltration rates are presented in the following table:

Infiltration Rates Summary

Boring No.	Depth Below Finish Grade (feet)	Factored Observed Infiltration Rates (inches/hour) *
I-1	5.0	0.74

**Rates incorporate a minimum factor safety of 2.*

The results of the infiltration testing indicate that the site is suitable for infiltration of stormwater, provided that the recommendations presented herein and the requirements of the County of San Bernardino are implemented during design and construction.

Excavation Characteristics

The majority of the soil materials underlying the site can be excavated with excavators and other conventional grading equipment.

GEOTECHNICAL ENGINEERING CONCLUSIONS AND RECOMMENDATIONS

Conclusions

Based on the results of our field exploration and engineering analyses, it is our opinion that the proposed development is feasible from a geotechnical standpoint, provided that the recommendations in this report are incorporated into the design plans and are implemented during construction.

The proposed residence may be supported on shallow spread foundation system embedded a minimum of 18 inches into competent engineered fill. Due to the compressible near-surface material encountered during our subsurface investigation, the potential for soil subsidence in the upper 3 feet, and potential disturbance of subsurface soils during grading, we recommend that the building pad be excavated to a depth of 3 below the existing grade and recompacted to create a uniform blanket of engineered fill.

Our geotechnical engineering analyses performed for this report were based on the earth materials encountered during the subsurface exploration for the site. If the design substantially changes, then our geotechnical engineering recommendations would be subject to revision based on our evaluation of the changes. The following sections present our conclusions and recommendations pertaining to the engineering design for this project.

Site Preparation

Site preparation should begin with the removal of utility lines, asphalt, concrete, vegetation, and other deleterious debris from areas to be graded. Tree stumps and roots should be removed to such a depth that organic material is generally not present. Clearing and grubbing should extend to the outside edges of the proposed excavation and fill areas. We recommend that unsuitable materials such as organic matter or oversized material be selectively removed and disposed offsite. The debris and unsuitable material generated during clearing and grubbing should be removed from areas to be graded and disposed at a legal dump site away from the project area.

Remedial Grading

Due to the dry / loose nature of the near surface soils, we recommend that the upper 3 feet of the site soils be removed and recompacted to achieve a uniform blanket of properly moisture conditioned and compacted fill material prior to placement of new fill or new foundation.

It should be noted that the recommendations provided herein are based on our subsurface exploration and knowledge of the on-site geology. Actual removals may vary in configuration and volume based on observations of geologic materials and conditions encountered during grading. The bottom of all corrective grading removals should be observed by a representative of NTS to verify the suitability of in-place soil prior to performing scarification and recompaction. Remedial grading recommendations are outlined below.

Fill Areas:

Areas to receive structural fill should be prepared by removing organic growth from the pad surface and other existing improvements. These areas should then be moisture conditioned to at least 2 percent above optimum to a depth of 3 feet below the existing grade, and should be compacted to achieve 90 percent relative compaction. A representative of NTS should be onsite to determine the actual depth of removal and perform compaction testing to verify the required moisture compaction is achieved in the field. Fill placed above the existing grade should be placed in accordance with the Compacted Fill section of this report.

Cut Areas:

Areas that are planned to be cut should be thoroughly watered after the proposed cuts are made to obtain a moisture content that is 2 percent above optimum moisture content to a depth of 3 feet below the finish grade. The moisture conditioned soil should be compacted to at least 90 percent relative compaction. Wherever a building pad spans a cut/fill transition, then the building pad area should be overexcavated to a depth of 3 feet below the footing and recompacted to achieve a uniform blanket of compacted fill.

Building Pads

In order to create a firm and stable platform on which to construct the new building pads, we recommend the following:

- The proposed building pads should be excavated to a depth of at least 2 feet from finish rough grade.
- The bottom of the over excavation should then be scarified to a depth of at least 8 inches, thoroughly flooded to raise the moisture content of the underlying soils to at least 2 percent above optimum moisture content, and should be recompacted using heavy vibratory compaction equipment prior to placement of any fill.
- Following the approval of the over-excavation bottom by a representative of NTS, the onsite material may be used as fill material to achieve the planned pad grade.
- The fill material should then be placed in 6- to- 8-inch-thick lifts, moisture conditioned to near optimum moisture content and compacted to achieve 90 percent relative compaction.

Parking Lots

In order to create a firm and stable platform on which to construct the new vehicular pavement, we recommend the following:

- The proposed pavement should be excavated to the planned subgrade (i.e., bottom of aggregate base for pavement).
- The bottom of the excavation should then be scarified to a depth of 12 inches below the planned subgrade.
- The bottom of the over excavation should then be scarified to a depth of at least 6 inches, moisture conditioned to 2 percent above optimum moisture content and recompacted to at least 90 percent relative compaction as determined in accordance with ASTM D1557.
- Following the approval of the over-excavation bottom by a representative of NTS, the onsite material may be used as fill material to achieve the planned pad grade.
- The fill material should then be placed in 6- to- 8-inch-thick lifts, moisture conditioned to near optimum moisture content and compacted to achieve 90 percent relative compaction.

If the existing loose fill materials are found to be disturbed to depths greater than the proposed remedial grading, then the depth of over-excavation and re-compaction should be increased accordingly in local areas as recommended by a representative of NTS.

Materials for Fill

On-site soils with an organic content of less than 3 percent by volume (or 1 percent by weight) are suitable for use as fill. Soil material to be used as fill should not contain contaminated materials, rocks, or lumps over 6 inches in largest dimension, and not more than 40 percent larger than $\frac{3}{4}$ inch. Utility trench backfill material should not contain rocks or lumps over 3 inches in largest dimension. Larger chunks, if generated during excavation, may be broken into acceptably sized pieces or may be disposed offsite.

Any imported fill material should consist of granular soil having a “very low” expansion potential (that is, expansion index of 20 or less). Import material should also have low corrosion potential (that is, chloride content less than 500 parts per million [ppm], soluble sulfate content of less than 0.1 percent, and pH of 5.5 or higher). Materials to be used as fill should be evaluated by a representative of NTS prior to importing or filling.

Compacted Fill

Prior to placement of compacted fill, the contractor should request an evaluation of the exposed excavation bottom by NTS. Unless otherwise recommended, the exposed ground surface should then be scarified to a depth of at least 6 inches and watered or dried, as needed, to achieve generally consistent moisture contents approximately near optimum moisture content. The scarified materials should then be compacted to 90 percent relative compaction in accordance with the latest version of ASTM Test Method D1557.

Compacted fill should be placed in horizontal lifts of approximately 6 to 8 inches in loose thickness. Prior to compaction, each lift should be watered or dried as needed to achieve near optimum moisture condition, mixed, and then compacted to a relative compaction of 90 percent as evaluated by ASTM D1557. Successive lifts should be treated in a like manner until the desired finished grades are achieved.

Personnel from NTS should observe the excavations so that any necessary modifications based on variations in the encountered soil conditions can be made. All applicable safety requirements and regulations, including CalOSHA requirements, should be met.

Temporary Excavations

Temporary excavations for the demolishing, earthwork, footing and utility trench are expected. We anticipate that unsurcharged excavations with vertical side slopes less than 3 feet high will generally be stable; however, sloughing of cohesionless sandy materials encountered at the site should be expected.

Where the space is available, temporary, unsurcharged excavation sides over 3 feet in height should be sloped no steeper than an inclination of 1H:1V (horizontal:vertical). Where sloped excavations are created, the tops of the slopes should be barricaded so that vehicles and storage loads do not encroach within 10 feet of the top of the excavated slopes. A greater setback may be necessary when considering heavy vehicles, such as concrete trucks and cranes. NTS should be advised of such heavy vehicle loadings so that specific setback requirements can be established. If the temporary construction slopes are to be maintained during the rainy season, berms are recommended to be graded along the tops of the slopes in order to prevent runoff water from entering the excavation and eroding the slope faces. Where space for sloped excavations is not available, temporary shoring may be utilized.

Personnel from NTS should observe the excavation so that any necessary modifications based on variations in the encountered soil conditions can be made. All applicable safety requirements and regulations, including CalOSHA requi

Building Foundation Design and Construction

A shallow foundation system may be used for support of the proposed buildings, provided that all the footings are embedded into competent engineered fill. Our geotechnical foundation design parameters are presented in the table below:

Bearing Material	<ul style="list-style-type: none"> ▪ Competent engineered fill ▪ See Remedial Grading section
Minimum Footing Size	<ul style="list-style-type: none"> ▪ Width: 12 inches ▪ Depth: 18 inches below the lowest adjacent soil grade
Minimum Footing Reinforcement	<ul style="list-style-type: none"> ▪ Footings reinforcement should consist of at least four No. 5 bars (two on top and two on bottom).
Allowable Bearing Capacity	<ul style="list-style-type: none"> ▪ 2,000 psf for the minimum footing size given above. ▪ The above value may be increased by 1/3 for temporary loads such as wind or earthquake.
Static Settlement	<ul style="list-style-type: none"> ▪ Total static settlement of 1 inch with differential settlement estimated to be approximately 1/2 inch over a span of 20 feet.
Allowable Lateral Passive Resistance	<ul style="list-style-type: none"> • 250 pcf (equivalent fluid pressure)
Allowable Coefficient of Friction	<ul style="list-style-type: none"> • 0.35

Slab-On-Grade Design and Construction

The slab-on-grade should be designed and constructed with the minimum recommendations presented below, however, final design of the slab should be determined by the project structural engineer.

Minimum Thickness: The minimum slab thickness should be 5 inches.

Minimum Slab Reinforcement: Minimum slab reinforcement shall not be less than No. 4 bars placed at 18 inches on center. Welded wire mesh is not recommended. Care should be taken to position the reinforcement bars in the center of the slab.

Slab Subgrade:

- The upper 24 inches of the slab subgrade should be moisture conditioned to near optimum moisture content and compacted to a minimum relative compaction of compacted to 90 percent relative compaction in accordance with the latest version of ASTM D1557.

- A moisture vapor retarder should be placed in accordance with the “Moisture Vapor Retarder” section below.

Moisture Vapor Retarder

A vapor retarder, such as a 10-mil-thick moisture vapor retarder that meets the requirements of ASTM E1745 Class C (Stego Wrap or equivalent) should be placed directly over the prepared soil subgrade to provide protection against vapor transmission through concrete floor slabs that are anticipated to receive carpet, tile or other moisture sensitive coverings. The use of moisture vapor retarder should be determined by the project architect. At minimum, the vapor retarder should be installed as follows:

- Per the manufacture’s specifications as well as with the applicable recognized installation procedures such as ASTM E1643;
- Joints between the sheets and the openings for utility piping should be lapped and taped. If the barrier is not continuously placed across footings/ribs, the barrier should at minimum be lapped into the side of the footing/rib trenches down to the bottom of the trench; and,
- Punctures in the vapor retarder should be repaired prior to concrete placement.

It should be noted that the moisture retarder is intended only to reduce moisture vapor transmissions from the soil beneath the concrete and is consistent with the current standard of the industry in the building construction in Southern California. It is not intended to provide a “waterproof” or “vapor proof” barrier or reduce vapor transmission from sources above the retarder (i.e., concrete). The evaluation of water vapor from any source and its effect on any aspect of the proposed building space above the slab (i.e., floor covering applicability, mold growth, etc.) is beyond our purview and the scope of this report.

Preliminary Infiltration Design and Construction Recommendations

The following recommendations should be considered during design and construction of the proposed BMP system:

- The selected infiltration BMP should be designed and constructed in accordance with the minimum requirements presented below, the requirements of the County of San Bernardino.

Minimum Setback Requirements

Property lines and public right of way	<ul style="list-style-type: none"> A minimum of 10 feet setback.
Any foundation	<ul style="list-style-type: none"> A minimum of 10 feet setback or within 1:1 plane drawn up from the bottom of foundation, whichever is greater.
Water wells used for drinking water	<ul style="list-style-type: none"> A minimum of 100 feet setback.

- The final design and specification should be reviewed by the Geotechnical Engineer of Record prior to construction to verify compliance with the recommendations of this report and/or provide additional recommendations/revisions, if needed.

Asphalt Concrete Pavement Design

In accordance with Chapter 600 of the Caltrans Highway Design Manual, we have performed pavement structural design utilizing assumed traffic indices (TI) of 5.5 and 6.0 and assumed R-value of 30. Based on our analysis, we have developed the pavement structural sections presented in the following table. We note that the assumed TI's should be reviewed by a traffic engineer to confirm their applicability to the project. Additionally, the R-value testing should be performed at the completion of rough grading of the pavement to confirm the pavement thickness provided herein.

Asphalt Concrete Pavement Structural Sections

Location	Traffic Index	Asphalt Concrete (in.)	Aggregate Base (in.)*
Driveways	5.5	4.0	5.0
Private Streets	6.0	4.0	6.0

The planned pavement structural sections should consist of the following:

- Aggregate Base materials (AB) consisted of either Crushed Aggregate Base (CAB) or Crushed Miscellaneous Base (CMB).
- Asphalt Concrete (AC) material of a type meeting the minimum Town of Yucca Valley standards.
- The subgrade soils should be moisture conditioned to near optimum moisture content to a depth of at least 18 inches and compacted to 90 percent relative compaction.

- The AB and AC should be compacted to at least 95 percent relative compaction.

Exterior Flatwork/Hardscape Design Considerations

For exterior flatwork and hardscape planned as part of the proposed development, the following design may be considered by the project civil engineer. These recommendations may be considered as minimal design based on the soils conditions encountered during our investigation. Final design of the proposed flatwork and hardscape area should be provided by the project civil engineer. Based on the conditions encountered, we recommend that the subgrade for the subject concrete flatwork and hardscape be moisture conditioned to near optimum to a depth of 18 inches below finish subgrade elevation and compacted to 90 percent relative compaction. A Type II/V cement may be used from a geotechnical perspective. Our flatwork and hardscape design considerations are presented in the table below.

Concrete Flatwork Table

Description	Subgrade Preparation ⁽¹⁾	Minimum Concrete Thickness	Cut-Off Barrier Or Edge Thickness	Joint Spacing (Maximum)	Concrete ⁽³⁾
Concrete Sidewalks and Walkways ⁽⁴⁾	1) 2 percent above optimum to 12" ⁽¹⁾ , 2) 2" of sand or well graded rock (i.e., Class II base or equiv.) above moisture conditioned subgrade.	4 inches	Not Required	5 feet	Type II/V

- (1) The moisture content of the subgrade must be verified by the geotechnical consultant prior to sand/rock placement.
- (2) Reinforcement to be placed at or above the mid-point of the slab (i.e., a minimum of 2.0 to 2.5 inches above the prepared subgrade).
- (3) The site has negligible levels of sulfates as defined by the CBC. Concrete mix design is outside the geotechnical engineer's purview.
- (4) Where flatwork is adjacent a stucco surface, a ¼" to ½" foam separation/expansion joint should be used.
- (5) If dowels are placed in cored holes, the core holes shall be placed at alternating in-plane angles (i.e., not cored straight into slab).

Planters and Trees

Where new trees or large shrubs are to be located in close proximity to new concrete flatwork, rigid moisture/root barriers should be placed around the perimeter of the flatwork to at least 12 inches in depth in order to offer protection to the adjacent flatwork against potential root and moisture damage. Existing

mature trees near flatwork areas should also incorporate a rigid moisture/root barrier placed at least 2 feet in depth below the top of the flatwork.

Drainage Control

The control of surface water is essential to the satisfactory performance of the building and site improvements. Surface water should be controlled so that conditions of uniform moisture are maintained beneath the improvements, even during periods of heavy rainfall. The following recommendations are considered minimal:

- Ponding and areas of low flow gradients should be avoided.
- If bare soil within 5 feet of the structure is not avoidable, then a gradient of 5 percent or more should be provided sloping away from the improvement. Corresponding paved surfaces should be provided with a gradient of at least 2 percent.
- The remainder of the unpaved areas should be provided with a drainage gradient of at least 2 percent.
- Positive drainage devices, such as graded swales, paved ditches, and/or catch basins should be employed to accumulate and to convey water to appropriate discharge points.
- Concrete walks and flatwork should not obstruct the free flow of surface water.
- Brick flatwork should be sealed by mortar or be placed over an impermeable membrane.
- Area drains should be recessed below grade to allow free flow of water into the basin.
- Enclosed raised planters should be sealed at the bottom and provided with an ample flow gradient to a drainage device. Recessed planters and landscaped areas should be provided with area inlet and subsurface drain pipes.
- Planters should not be located adjacent to the structures wherever possible. If planters are to be located adjacent to the structures, the planters should be positively sealed, should incorporate a subdrain, and should be provided with free discharge capacity to a drainage device.
- Planting areas at grade should be provided with positive drainage. Wherever possible, the grade of exposed soil areas should be established above adjacent paved grades. Drainage devices and curbing should be provided to prevent runoff from adjacent pavement or walks into planted areas.
- Gutter and downspout systems should be provided to capture discharge from roof areas. The accumulated roof water should be conveyed to off-site disposal areas by a pipe or concrete swale system.
- Landscape watering should be performed judiciously to preclude either soaking or desiccation of soils. The watering should be such that it just

sustains plant growth without excessive watering. Sprinkler systems should be checked.

Plans and Specifications Review

The recommendations presented in this report are contingent upon review of final plans and specifications for the project by NTS. NTS Geotechnical, Inc. should review and verify in writing the compliance of the final grading plan and the final foundation plans with the recommendations presented in this report.

Construction Observation and Testing

It is recommended that NTS be retained to provide Geotechnical Consulting services during the earthwork operations and foundation installation process. This is to observe compliance with the design concepts, specifications and recommendations and to allow for design changes in the event that subsurface conditions differ from those anticipated during our subsurface investigation.

It is the responsibility of the owner and their representative to bring any deviations or unexpected conditions observed during construction to the attention of NTS Geotechnical, in order for supplemental recommendations can be made with a minimum delay to the project. Construction should be observed and/or testing at the following stages by NTS Geotechnical, Inc.:

- During all phases of precise grading, including over-excavation, temporary excavations, removals, scarification, ground preparation, moisture condition, proof-rolling, and placement and compaction of all fill material.
- All foundation excavation prior to placement of steel
- When unusual conditions are encountered.

If any of these inspections to verify site geotechnical conditions are not performed by NTS Geotechnical, liability for the safety and stability of the project is limited only to the actual portions of the project that is observed and approved by NTS Geotechnical.

LIMITATIONS

All parties reviewing or utilizing this report should recognize that the findings, conclusions, and recommendations presented represent the results of our professional geological and geotechnical engineering efforts and judgments. Due to the inexact nature of the state of the art of these professions and the possible occurrence of undetected variables in subsurface conditions, we cannot guarantee that the conditions actually encountered during grading and site construction will be identical to those observed, sampled, and interpreted during our study, or that there are no unknown subsurface conditions which could have

an adverse effect on the use of the property. We have exercised a degree of care comparable to the standard of practice presently maintained by other professionals in the fields of geotechnical engineering and engineering geology, and believe that our findings present a reasonably representative description of geotechnical conditions and their probable influence on the grading and use of the property.

Our conclusions and recommendations are based on the assumption that our firm will act as the geotechnical engineer of record during construction and grading of the project to observe the actual conditions exposed, to verify our design concepts and the grading contractor's general compliance with the project geotechnical specifications, and to provide our revised conclusions and recommendations should subsurface conditions differ significantly from those used as the basis for our conclusions and recommendations presented in this report. Since our conclusions and recommendations are based on a limited amount of current and previous geotechnical exploration and analysis, all parties should recognize the need for possible revisions to our conclusions and recommendations during grading of the project.

It should be further noted that the recommendations presented herein are intended solely to minimize the effects of post-construction soil movements. Consequently, minor cracking and/or distortion of all on-site improvements should be anticipated.


This report has not been prepared for the use by other parties or projects other than those named or described herein. This report may not contain sufficient information for other parties or other purposes.

REFERENCES

Coduto, Donald P., 1994, Foundation Design: Principles and Practices: Prentice-Hall, Inc, Englewood Cliffs, New Jersey.

County of San Bernardino Land Use Plan, General Plan, Geologic Hazard Overlays.

Naval Facilities Engineering Command, 1986, NAVFAC Design Manual.



SITE LOCATION




LOCATION MAP

NTS
GEOTECHNICAL


Date: April 13th, 2023

Project No.: 23143

Plate
1



CONSTRUCTION NOTE:
 ① PROPOSED 0" CURB
 ② PROPOSED 5" DECOMPOSE GRANITE OVER AB (CLASS II)
 ③ PROPOSED 4" DECOMPOSE GRANITE WALKWAY



GEOTECHNICAL LEGEND

- B-1** ● APPROXIMATE LOCATION OF BORING
- P-1** ● APPROXIMATE LOCATION OF PERCOLATION TEST
- I-1** ● APPROXIMATE LOCATION OF INFILTRATION TEST

GEOTECHNICAL MAP

Date: 05/05/2023 Project No.: 23143 Plate: 2

APPENDIX A

Field Exploration

Appendix A Field Exploration

The subsurface exploration program for the proposed project consisted of advancing five (5) 8-inch-diameter, hand tool borings at the subject site. The borings were advanced to depths ranging from 10 to 15 feet below the existing grade. The logs are presented within Appendix A.

The Boring Logs are presented as Figures A-2 to A-6. The Boring Logs describe the earth materials encountered, samples obtained, and show the field and laboratory tests performed. The log also shows the boring number, drilling date, and the name of the logger and drilling subcontractor. The borings were logged by an engineer using the Unified Soil Classification System. The boundaries between soil types shown on the logs are approximate because the transition between different soil layers may be gradual. Drive and bulk samples of representative earth materials were obtained from the borings.

A California modified sampler was used to obtain drive samples of the soil encountered. This sampler consists of a 3-inch outside diameter (O.D.), 2.4-inch inside diameter (I.D.) split barrel shaft that was driven a total of 6-inches into the soil at the bottom of the boring by a safety hammer. The soil was retained in brass rings for laboratory testing. Additional soil from each drive remaining in the cutting shoe was usually discarded after visually classifying the soil.

Upon completion of the borings, the boreholes were backfilled with soil from the cuttings.

Project: **5022 Lomita Lane**
 Project Location: 5022 Lomita Lane, Yucca Valley
 Project Number: 23143



Key to Log of Boring
 Sheet 1 of 1

1	2	3	4	5	6	7	8	9
Depth (feet)	Sample Type	Sampling Resistance, blows/ft	Material Type	Graphic Log	MATERIAL DESCRIPTION	Water Content, %	Dry Unit Weight, pcf	REMARKS AND OTHER TESTS

COLUMN DESCRIPTIONS

- 1** Depth (feet): Depth in feet below the ground surface.
- 2** Sample Type: Type of soil sample collected at the depth interval shown.
- 3** Sampling Resistance, blows/ft: Number of blows to advance driven sampler one foot (or distance shown) beyond seating interval using the hammer identified on the boring log.
- 4** Material Type: Type of material encountered.
- 5** Graphic Log: Graphic depiction of the subsurface material encountered.
- 6** MATERIAL DESCRIPTION: Description of material encountered. May include consistency, moisture, color, and other descriptive text.
- 7** Water Content, %: Water content of the soil sample, expressed as percentage of dry weight of sample.
- 8** Dry Unit Weight, pcf: Dry weight per unit volume of soil sample measured in laboratory, in pounds per cubic foot.
- 9** REMARKS AND OTHER TESTS: Comments and observations regarding drilling or sampling made by driller or field personnel.


FIELD AND LABORATORY TEST ABBREVIATIONS

- CHEM: Chemical tests to assess corrosivity
- COMP: Compaction test
- CONS: One-dimensional consolidation test
- LL: Liquid Limit, percent
- PI: Plasticity Index, percent
- SA: Sieve analysis
- DS: Direct Shear
- EI: Expansion Index
- WA: Wash sieve (percent passing No. 200 Sieve)


MATERIAL GRAPHIC SYMBOLS



TYPICAL SAMPLER GRAPHIC SYMBOLS



OTHER GRAPHIC SYMBOLS



GENERAL NOTES

- 1: Soil classifications are based on the Unified Soil Classification System. Descriptions and stratum lines are interpretive, and actual lithologic changes may be gradual. Field descriptions may have been modified to reflect results of lab tests.
- 2: Descriptions on these logs apply only at the specific boring locations and at the time the borings were advanced. They are not warranted to be representative of subsurface conditions at other locations or times.

C:\Users\Mary_Dee\NTS GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log Data.bgd\NTS Template_1-9-21.rpt

Figure A-1

Project: 5022 Lomita Lane		Log of Boring B-1
Project Location: 5022 Lomita Lane, Yucca Valley		Sheet 1 of 1
Project Number: 23143		

Date(s) Drilled: 03/23/2023	Logged By: ERL	Checked By: NS
Drilling Method: Hollow Stem Auger	Drill Bit Size/Type: 8"	Total Depth of Borehole: 10 feet
Drill Rig Type: CME 75	Drilling Contractor: OWD	Approximate Surface Elevation: N/A
Groundwater Level and Date Measured: Not encountered	Sampling Method(s): Modified California, SPT	Hammer Data: 140-lb autohammer
Borehole Backfill: Native	Location: 4942 Lomita Lane, Yucca Valley	





Figure A-2

Project: 5022 Lomita Lane		Log of Boring B-2
Project Location: 5022 Lomita Lane, Yucca Valley		Sheet 1 of 1
Project Number: 23143		

Date(s) Drilled: 03/23/2023	Logged By: ERL	Checked By: NS
Drilling Method: Hollow Stem Auger	Drill Bit Size/Type: 8"	Total Depth of Borehole: 10 feet
Drill Rig Type: CME 75	Drilling Contractor: OWD	Approximate Surface Elevation: N/A
Groundwater Level and Date Measured: Not encountered	Sampling Method(s): Modified California, SPT	Hammer Data: N/A
Borehole Backfill: Native	Location: 4942 Lomita Lane, Yucca Valley	



C:\Users\Mary_Dee\NTS_GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log_Data.bg4[NTS Template_1-9-21.tpl]

Figure A-3

Project: 5022 Lomita Lane		Log of Boring B-3
Project Location: 5022 Lomita Lane, Yucca Valley		Sheet 1 of 2
Project Number: 23143		

Date(s) Drilled: 03/23/2023	Logged By: ERL	Checked By: NS
Drilling Method: Hollow Stem Auger	Drill Bit Size/Type: 8"	Total Depth of Borehole: 15 feet
Drill Rig Type: CME 75	Drilling Contractor: OWD	Approximate Surface Elevation: N/A
Groundwater Level and Date Measured: Not encountered	Sampling Method(s): Modified California, SPT	Hammer Data: N/A
Borehole Backfill: Native	Location: 4942 Lomita Lane, Yucca Valley	

Depth (feet)	Sample Type	Sampling Resistance, blows/ft	Material Type	Graphic Log	MATERIAL DESCRIPTION	Water Content, %	Dry Unit Weight, pcf	REMARKS AND OTHER TESTS
0			SM		ALLUVIUM (Qa); SILTY SAND, fine to coarse-grained sand, medium dense, dry, brown			
28						3	116	
5			SM		very dense			
74								
10			SM		dense, dry			
48						3	122	
15								

C:\Users\Mary_Dee\NTS_GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log_Data.bg4[NTS Template_1-9-21.tpl]

Figure A-4

Project: **5022 Lomita Lane**
 Project Location: 5022 Lomita Lane, Yucca Valley
 Project Number: 23143



Log of Boring B-3
 Sheet 2 of 2

Depth (feet)	Sample Type Sampling Resistance, blows/ft	Material Type	Graphic Log	MATERIAL DESCRIPTION	Water Content, %	Dry Unit Weight, pcf	REMARKS AND OTHER TESTS
15	38	SM		some gravel, broken pieces of rock, dense Total Depth = 15 feet Groundwater not encountered Backfilled with native			
50							

C:\Users\Mary_Dee\NTS_GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log Data.bg4[NTS Template_1-9-21.tpl]

Figure A-4

Project: 5022 Lomita Lane		Log of Boring B-4
Project Location: 5022 Lomita Lane, Yucca Valley		Sheet 1 of 2
Project Number: 23143		

Date(s) Drilled: 03/23/2023	Logged By: ERL	Checked By: NS
Drilling Method: Hollow Stem Auger	Drill Bit Size/Type: 8"	Total Depth of Borehole: 15 feet
Drill Rig Type: CME 75	Drilling Contractor: OWD	Approximate Surface Elevation: N/A
Groundwater Level and Date Measured: Not encountered	Sampling Method(s): Modified California, SPT	Hammer Data: N/A
Borehole Backfill: Native	Location: 4942 Lomita Lane, Yucca Valley	

Depth (feet)	Sample Type	Sampling Resistance, blows/ft	Material Type	Graphic Log	MATERIAL DESCRIPTION	Water Content, %	Dry Unit Weight, pcf	REMARKS AND OTHER TESTS
0			SM		ALLUVIUM (Qa); SILTY SAND, few pebbles, fine to coarse-grained sand, medium dense, damp, brown			
23		23				4	120	
5		47	SM		very dense			
10		98/11"	SM		very dense, damp	5	125	
15								

C:\Users\Mary_Dee\NTS - GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log_Data.bg4[NTS Template_1-9-21.tpl]

Figure A-5

Project: **5022 Lomita Lane**
 Project Location: 5022 Lomita Lane, Yucca Valley
 Project Number: 23143



Log of Boring B-4
 Sheet 2 of 2


Depth (feet)	Sample Type	Sampling Resistance, blows/ft	Material Type	Graphic Log	MATERIAL DESCRIPTION	Water Content, %	Dry Unit Weight, pcf	REMARKS AND OTHER TESTS
15	SM	55	SM		fine to coarse-grained sand, very dense, light brown to tan Total Depth = 15 feet Groundwater not encountered Backfilled with native			
20								
25								
30								
35								
40								
45								
50								

C:\Users\Mary_Dee\NTS_GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log Data.bg4[NTS Template_1-9-21.tpl]

Figure A-5

Project: 5022 Lomita Lane		Log of Boring B-5
Project Location: 5022 Lomita Lane, Yucca Valley		Sheet 1 of 1
Project Number: 23143		

Date(s) Drilled: 03/23/2023	Logged By: ERL	Checked By: NS
Drilling Method: Hollow Stem Auger	Drill Bit Size/Type: 8"	Total Depth of Borehole: 10 feet
Drill Rig Type: CME 75	Drilling Contractor: OWD	Approximate Surface Elevation: N/A
Groundwater Level and Date Measured: Not encountered	Sampling Method(s): Modified California, SPT	Hammer Data: N/A
Borehole Backfill: Native	Location: 4942 Lomita Lane, Yucca Valley	



C:\Users\Mary_Dee\NTS GEOTECHNICAL\Projects - General\2023\23143 - 4942 Lomita Lane, Yucca Valley\Reports\Appendix A\23143 Boring Log_Data.bg4[NTS Template_1-9-21.tpl]

Figure A-6

APPENDIX B

Laboratory Testing Data

Appendix B Geotechnical Laboratory Testing

Laboratory Moisture Content and Density Tests

The moisture content and dry densities of selected driven samples obtained from the exploratory boring was evaluated in general accordance with the latest version of ASTM D 2937. The test results are presented on the log of the exploratory boring in Appendix A.

Grain Size Analysis

The number of fines passing the No. 200 sieve was evaluated by the wash sieve. The test procedure was in general accordance with ASTM D422. The results are attached to this Appendix B.

Boring No.	Depth (ft)	Soil Description	Fines Passing No. 200, %
B-1	5	Qa	28
B-4	15	Qa	30

Corrosion Suite

The corrosion potential of typical on-site materials under long-term contact with both metal and concrete was determined by chemical and electrical resistance tests. The soluble sulfate test for potential concrete corrosion was performed in general accordance with ASTM D4327. The test results are attached to this Appendix B.

Boring No.	Depth (feet)	pH	As-Is-Soil Resistivity (ohm-cm)	Minimum Soil Resistivity (ohm-cm)	Chloride (ppm)	Sulfate (ppm)
B-4	2.0	7.34	20,000	6,000	70	40

Direct Shear Tests

Direct shear tests were performed on selected remolded and relatively undisturbed soil samples in general accordance with ASTM D 3080 to evaluate the shear strength characteristics of the materials. The samples were inundated during shearing to represent adverse field conditions. Direct shear test results are attached to this Appendix B.

Consolidation Test


Consolidation tests was performed on a selected driven soil sample in general accordance with the latest version of ASTM D2435. The sample was inundated during testing to represent adverse field conditions. The percent consolidation for each load cycle was recorded as a ratio of the amount of vertical compression to the original height of the sample. Consolidation testing results are attached to this Appendix B.

PLATE: S-1
 P.N. 23143

Direct Shear Test Diagram (D-3080)

Sample Description	Sample Identification	Test Type	Sample Test State	Number of Passes
Qa	B-1 @ 2.0'	Ultimate	Saturated	1


Soil Dry Density (PCF)	120	Shear Strength Values:	
Soil Moisture Content (%)	14	Phi (Degrees)	29.0
Soil Saturation (%)	98.1	Cohesion (PSF)	148.3



Consolidation Pressure Curve (D-2435)

Sample Identification	Sample Description
B-1 @ 10.0'	Qa


PLATE: C-1
P.N. 23143



Consolidation Pressure Curve (D-2435)

Sample Identification	Sample Description
B-5 @ 5.0'	Qa

PLATE: C-2
P.N. 23143



APPENDIX C

Infiltration Test Data



Falling Head Borehole Infiltration Test

Project Name:	5022 Lomita Ln, Yucca Valley			Date:	3/23/2023
Project Number:	23143			Tested By:	ERL
Test Hole Number:	I-1			USCS Soil Classification:	SM
Total Depth :	5.00	feet			
Test Hole Diameter:	8.00	inches	radius=	4	inches

Trial	Start Time	End Time	ΔT	Total Time	Initial Depth of Water	Final Depth of Water	H_0	H_f	ΔH	H_{avg}	Unfactor ed Percolati
			(min)	(min)	(ft)	(ft)	(in)	(in)	(in)	(in)	(in/hour)
1	9:00	9:10	10.0	10.0	2.00	2.50	36.00	30.00	6.00	33.00	2.06
2	9:10	9:20	10.0	20.0	2.50	2.85	30.00	25.80	4.20	27.90	1.69
3	9:20	9:30	10.0	30.0	2.85	3.15	25.80	22.20	3.60	24.00	1.66
4	9:30	9:40	10.0	40.0	3.15	3.40	22.20	19.20	3.00	20.70	1.59
5	9:40	9:50	10.0	50.0	3.40	3.62	19.20	16.56	2.64	17.88	1.59
6	9:50	0:00	10.0	60.0	3.62	3.80	16.56	14.40	2.16	15.48	1.48

SAFETY FACTOR:	2
UNFACTORED INFILTRATION RATE (IN/HR):	1.48
FACTORED INFILTRATION RATE (IN/HR):	0.74